BRUHATH BENGALURU MAHANAGARA PALIKE,DASARAHALLI ZONE

Office of Executive Engineer

SCHEDULE -B

Name Of Work: UGD works in ward no 13 Shettyhalli sub division

Sl. No	Descrption of Work	Unit	Qty	Sanctioned Rate	
				In Figures (Rs.)	In Wards (Rs.)
1	KSRB 2-2.2 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation after breaking of clods with all lead and lifts etc., complete as per specifications and directions of Engineer Incharge.. specification. No. KBS 2.1(b) / 2.3.5	Cum	579.8	475.00	
2	Stone dust / Grit with all lead and lifts etc., complete as per specifications and directions of Engineer Incharge..	Cum	109.8	1060.00	
3	KSRB 12.-1.1 : Providing and laying in position to required level or slope 230mm internal diameter salt glazed stoneware pipes grade A and jointing with stiff mixture of cement mortar in proportion of 1:1, testing of pipes and joints,including cost of materials, labour charges with all lead and lifts etc., complete as per specifications and directions of Engineer Incharge. Specification No. KBS 12.2.5/12.7	Mtr	366	568.00	
4	Filling available earth around pipe lines cable in layers not exceeding 20cms, in depth compacting each deposited layer by ramming after watering including cost all labour with all lead and lifts etc., complete as per specifications and directions of Engineer Incharge..	Cum	330.49	213.00	

Scanned by CamScanner

6	KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering with all lead and lifts etc., complete as per specifications and directions of Engineer Incharge..	Cum	54.9	5501.10	
7	Providing and laying cement concrete using 20 mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) M 20 for R.C.C works laid in 15 cms thick layers and well compacted vibrating, curing, for raft foundation and Sub Structures with all lead and lifts etc., complete as per specifications and directions of Engineer Incharge.(exclusive of cost of steel and fabrication charges.)	Cum	54.9	5880.00	

Signature of Contractor

Executive Engineer
Dasarahalli Division

Scanned by CamScanner